



Always check the website for the most updated specifications: www.americh.com




Tub pictured with optional waste & overflow




All bathtub dimensions are ± 1/2"


Builder Series



Luxury Series




Platinum Series




Combination



(pump and blower location only)



Airbath System II



Airbath System III



FOB: Charlotte, NC

INSTALLATION TIPS

- Install according to Owner's Manual and local codes. Always consult your local plumber for recommendations.
 - Certain options or altering the pump/blower location may cause the pump/blower to extend beyond the tub decking.
 - Airbath III units may be 1 1/2" – 2 1/2" taller than stated.
 - Hot water supply should be 65-75% of the tub capacity or greater.
 - Cut Dimensions: 64"x28" It is recommended to wait for unit to arrive before cutting
 - All specifications are subject to change without notice
- ++ Factory installed aprons on this model may increase the overall height of the tub when ordered with certain accessories (.IE Linear Drain)

DIMENSIONS

66" x 30" x 18" (1676 x 762 x 457 mm)
 Whirlpool Operating Gallons = 45 (Liters = 170)
 Gallon to Overflow = 62 (Liters = 235)

MATERIAL: Acrylic (All Americh Standard Colors)

TUB FLOOR: Textured

UNDERMOUNT: Yes

- Advise Americh when ordering to ensure there are no issues with deck mounted controls.
- Always take dimensions directly from the unit.

ELECTRICAL REQUIREMENTS

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

OPTIONAL ACCESSORIES

- Apron (flat non-removable) ++
- Chromatherapy*
- Grab Bars: 9" - 14" * - 16"
- High Density Insulation*
- iBath Sound System
- Inline Heater (whirlpool only)
- Jets: Additional or Rotary*
- Lo Profile Tub Edge
- Ozone System (whirlpool and/or Airbath only)
- Pillows: 13" *
Angle - Full Back
- Remote Control Upgrade (select series only)
- Serenity Soak (tub only)
- Syllent Pump with Heated Air*
- Tile Flange Kit
- Trim Kit Upgrade*
- Waste & Overflow
 - Cable Drive Overflow*
 - Linear Overflow

*Standard on Platinum Series

CODES AND COMPLIANCE

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories - Canada (cUL)
- Canadian Standards Association - (CSA)
- ANSI Z124.1 • ANSI A112-19.7
- ANSI A112.19.8 • ASTM F462-79

Contact Americh for additional approvals.